



## Public Works Department

Engineering • Facilities  
Solid Waste • Storm Water • Street • Traffic

December 10, 2012

### ADDENDUM NO. 3

ITB: 5636

PIN: 041039.00

Federal Project No.: IVHS-9447-(402)

State Project No.: 90952-1642-54

1. On the Bid Form in the *Proposal Contract* and in the Estimated Quantities on Sheet 2 in the *Plan Set* and in *Addendum 2* the Item number 920-10.04 TMC Video Wall has a unit of "Each" which should read "**LS**"
2. *TSP 725 – Section 5* makes multiple references to a "4-Wire FSK Interface." All references to 4-Wire FSK in the bid book and plans are to be "**2-Wire FSK**" and pay Item Number "725-10.18" description is hereby modified in the technical specifications, bid form and quantities sheets in the plans (sheet 2, 2A, and 2B) to read "**RS 232 2 Wire FSK Modem**".
3. Plans sheet 2T typical for "*Pole Mounted Type B Field Cabinet*" identifies sunshields on the top and south facing sides of the cabinet (minimum). The sunshields are not required on any contractor supplied cabinet.
4. Cabinet Type B (Pay Item Numbers **725-10.12** and **725-10.13**) and Type C (Pay Item Number **725-10.51**) shall include ventilation with a field hardened ventilation fan with ball or roller bearings and a capacity of not less than 100 cubic feet per minute with thermostatic control. Cabinets provided with power shall have the thermostat and fan wired to be operational; cabinets without power shall have the thermostat and fan ready to be wired operational if power is supplied to the cabinet in the future. All references in *TSP 725 – Section 5* or elsewhere in the plans and specifications in conflict are overridden by this requirement.