



## Public Works Department

Engineering • Facilities  
Solid Waste • Storm Water • Street • Traffic

February 28, 2013

### ADDENDUM NO. 1

ITB: R5636

PIN: 041039.00

Federal Project No.: IVHS-9447(402)

State Project No.: 90952-1642-54

1. **TSP 725 – Section 8** The cameras are to be HD 720P. 18X optical zoom shall be the minimum acceptable for the tube type and the dome type cameras. This shall supersede any specifications in conflict.
2. **TSP 725 – Section 13.3.1 (5)** There will be 3 racks, not 4.
3. **TSP 725 – Section 17** This section on the Traffic Management Center describes the construction upgrades and required equipment and finishes needed and listed in Appendix A of Section 17. The cost and labor to install these items shall fall under the Items number 920-10.03 TMC Finishes. This includes the cost for all equipment and furniture listed in Appendix A and includes the cost removal and or rearranging of existing furniture to limit damage so the TMC construction can be completed.
4. **Item number 920-10.06 Sidewalk Replacement** This pay item is for the removal and replacement of sections of sidewalks that have been damaged due to the removal of existing pull boxes, the upgrade to pull boxes or has been damaged due to other construction on this project. The contractor should avoid damaging handicap ramps; no replacement of handicap ramps are anticipated.